



PRECAST CONCRETE
SANITARY MANHOLE

M.J. TEE

PROPOSED SANITARY
SEWER FORCE MAIN

INV. = ---
(2) 3/4" DIA.
TIE RODS

M.J.L.R. 90 BASE ELBOW

CONSTRUCT FORMED
CONCRETE CHANNEL
IN MANHOLE

BLIND FLANGE

(4) 3/4" DIA. S.S. ANCHORS

4" DIA. SCH. 80 STEEL
PIPE SUPPORT

--- PVC @ --- %

INV. = ---
(2) 5/8" DIA. THREADED RODS
AND EXPANSION ANCHORS DRILLED
INTO MANHOLE BASE

BY	DATE	REVISIONS

**TOWNSHIP OF FLORENCE
WATER & SEWER DEPARTMENT**

**FORCE MAIN
DISCHARGE MANHOLE**

DATE : **6/06**
DWN BY :